

BAHARI-1

F&G JU2000-E
3200 HP
OFFSHORE Rig

- **Related Drilling Depth**

30,000ft (9,144m) with 5 ½" drill pipe.

- **Hook Load**

1,600 kips (726 m.ton)

- **Setback Load**

950 kips (431 m.ton)

- **Derrick**

170 ft.

- **Drawwork**

ADS 10T, 3,000 hp (2,237 kw)

w/14 lines

- **Mud Pump Engine × Qty**

3 x 14-P-220, 2,200 hp, 7,500

psi

- **Travelling Equipment**

750 short ton (680 m.ton)

- **Rotary**

Varco RST 49.5

- **Top Drive**

Varco TDS-8SA-PH100 Pipe Handler

- **Well Control Equipment**

Cameron 15K: 18 ¾" & Cameron 3K:

203/4"

Vetco Gray KFDJ 500psi - 49 1/2"

Diverter

15000 psi Choke Manifold

- **CRANES & WINCHES**

Cranes 3 x Patriot , SWL 50m.ton

Overhead BOP crane SWL 125 s.ton

Bop Service Crane SWL 30 s.ton

Pipe handling systems Vertical

Knuckle Boom Crane

Tubular Handling system

- **Rig Power Supply**

Main Engines (5 CAT 1530kw, 690

volts) Emergency Engine (CAT

860kw, 480 Volts)

- **Drill String**

5 1/2" PMDS-FH S135 X 23000ft

- **Safety Equipment**

As required by regulations.