

Rig MDC21

XJ650S
650HP
Workover Rig

- **Substructure**

TZ147/5-Z, Height 5 m.

Hook Load

220,000 lbs. (8 Lines).

Setback Load

180,000 lbs

Mast

118ft.

- **Drawwork**

JC450-S, 650 HP & 1 1/8"

- **Auxiliary Brake**

Air Flex Eaton Friction disk

Rig Power Supply

1x CAT 3412 – 550 HP

Mud Pump Engine × Qty

NBQ25-380 1x CAT C15 - 540 HP

Travelling Equipment

YG150 150 Ton (8 Lines).

- **Rotary**

ZP175, 17 ½".

- **Well Control Equipment**

11" Annular Preventer 5000 psi.

11" double Ram preventer 5000 PSI 4

4 1/16" – 5000 psi Hydraulic & Manual

Chock Valves

4 1/16" – 5000 psi (2) Manual Kill Valves

- **Drill String**

3 ½ " , NC-38 , G105-13.30 lb/ft. (351
Drill String)

Safety Equipment

As required by regulations.