

Rig MDC22

XJ650S
650HP
Workover Rig

- **Substructure**

DZ 147/5-Z, Height 5 m.

- **Hook Load**

1575KN. (8 Lines).

- **Setback Load**

1600KN

- **Mast**

118ft.

- **Drawwork**

JC450-S, 650 HP & 1 1/8"

- **Auxiliary Brake**

Air Flex Eaton Friction disk

- **Rig Power Supply**

1x CAT 3412 – 550 HP

- **Mud Pump Engine × Qty**

1 NBQ25-380 1x CAT C15 - 540 HP

- **Travelling Equipment**

YG150 150 Ton (8 Lines).

- **Rotary**

ZP175, 17 ½".

- **Well Control Equipment**

11" Annular Preventer 5000 psi.

11" double Ram preventer 5000 PSI 4

4 1/16" – 5000 psi Hydraulic & Manual

Chock Valves

4 1/16" – 5000 psi (2) Manual Kill Valves

- **Drill String**

3 ½ " , NC-38 , G105-13.30 lb/ft. (351
Drill String)

- **Safety Equipment**

As required by regulations.