

Rig MDC23

XJ650S

650HP

Workover Rig

- **Substructure**

DZ147/5-Z, Height 5 m.

Hook Load

220,000 lbs. (8 Lines).

Setback Load

180,000 lbs

Mast

115ft.

- **Drawwork**

DC450-S, 650 HP & 1 1/8"

- **Auxiliary Brake**

Air Flex Eaton Friction disk

Rig Power Supply

1x CAT C15 - 540 HP

Mud Pump Engine × Qty

NBQ25-380 1x CAT C15 - 540 HP

Travelling Equipment

YG150 Ton (8 Lines).

- **Rotary**

ZP175, 17 1/2".

- **Well Control Equipment**

11 "Bag Preventer 5000 PSI

11" Ram double preventer Chinese

Drilling Spool: 11" – 5000 Psi

4 1/16" – 5000 psi Hydraulic & Manual
Chock Valves

4 1/16" – 5000 psi Manual Kill Valves

- **Drill String**

3 1/2" , NC-38 , G105-13.30 lb/ft. (267
Drill String)

Safety Equipment

As required by regulations.