

Rig MDC24

SXJ550

550HP

Workover Rig

- **Substructure**

DZ135 4.8, Height 5 m.

- Hook Load**

220,000 lbs. (8 Lines).

- Setback Load**

180,000 lbs

- Mast**

115ft.

- **Drawwork**

JC-550, 550 HP & 1"

- **Auxiliary Brake**

202 Hydro Brake.

- Rig Power Supply**

607 HP, CAT C-15.

540 HP, CAT C-15.

- Travelling Equipment**

YG150-4 Ton (8 Lines).

- **Rotary**

ZP175, 17 ½".

- **Well Control Equipment**

11 "Bag Preventer 5000 PSI

11" Ram double preventer Chinese

Drilling Spool: 11" – 5000 Psi

4 1/16" – 5000 psi Hydraulic & Manual
Chock Valves

4 1/16" – 5000 psi Manual Kill Valves

- **Drill String**

3 ½ " , NC-38 , G105-13.30 lb/ft. (285
Drill String)

- Safety Equipment**

As required by regulations.