

Rig MDC61

XJ550 (ZEPC)
550HP
Workover Rig

- **Substructure**

ZZT160, Height 5.65 m.

- **Hook Load**

1350 KN (8 Lines)

- **Setback Load**

900 KN

- **Mast**

JJ13535, 35 M.

- **Drawwork,**

JC15 , 550 HP & drilling line 1"

- **Auxiliary Brake**

PZ40 Hydraulic disc brake

- **Rig Power Supply**

1x CAT 15 – 540 HP

- **Mud Pump Engine × Qty**

1x CAT C27 - 652 KW

- **Travelling Equipment**

YG135B, 150 Ton (8 Lines).

- **Rotary**

ZX110A, 17 ½"

- **Well Control Equipment (SHENKAI)**

- 11 " Annular Preventer 3000 PSI
- 11" Double Ram preventer .
- Drilling Spool: 11" – 3000 Psi.
- 7 1/16" Annular Preventer 3000 PSI.
- 7 1/16" Double Ram preventer .
- Drilling Spool: 11" – 3000 Psi.
- 2 1/16" – 3000 psi Hydraulic & Manual Choke Valves .
- 2 1/16" – 3000 psi Manual Kill Valves.

- **Drill String**

3 ½ " , NC-38 , G105-13.30 lb/ft. (451 Drill String)

- **Safety Equipment**

As required by regulations.