Rig MDC12

JC70D Land Rig

- · Related Drilling Depth 20,000 ft with 5" drill pipe.
- Substructure DZ 450 / 10.5 - X, Height 10.5 m.
- Hook Load 1,000,000 lbs (12 lines).
- Setback Load 490,000 lbs.
- Mast 149.28 ft.
- Drawwork JC70D, 2000 HP & 1 1/2"
- Auxiliary Brake Faton436WCB2.
- Mud Pump Engine × Qty 2x1600 HP, F1600.
- Travelling Equipment YC450, 1,000,000 lbs.
- Rotary ZP375, 37 1/2".

Top Drive

Varco TDS 11SA or equiv, 500 Tons.

Well Control Equipment 13.5/8" Bag Preventer 5000 psi.

13.5/8" Ram single Preventer H2S service.

13.5/8" Ram double Preventer.

4 1/16" - 10000psi Hydraulic

4 1/16" - 10000psi Hydraulic Accumulator Unit, NXQ2-L 40/31.5H

Rig Power Supply

3x1600 HP Diesel Engine, CAT3512B. Power by 3x SR 4B 1900 KVA. [SCR]

Drill String

5", NC-50, 2" Weco, Lo-Torg 3.1/2", NC-38, 2" Weco, 2" Weco Safety Equipment As required by regulations.

Accommodation

To accommodate 80 persons.