## Rig MDC3

JC70D 2000 HP Land Rig

- Related Drilling Depth 20,000 ft with 5" drill pipe.
- Substructure
   DZ 450 / 10.5 X, Height 10.5m.
- Hook Load
   1,000,000 lbs (12 lines).
- Setback Load 490,000 lb.
- Mast 149.28 ft.
- Drawwork
   JC70D, 2000 HP & 1 ½"
- Auxiliary Brake
   Eaton436WCB2.
- Mud Pump Engine × Qty 2x1600 HP, F1600.
- Travelling Equipment YC450, 1,000,000 lbs.
- Rotary ZP375, 37 ½".

## Top Drive

Varco TDS 11SA or equiv., 500 Tons.

Well Control Equipment

13.5/8" Bag Preventer 10,000 psi.
13.5/8" Ram single Preventer H2S service.
13.5/8" Ram double Preventer.
4 1/16" – 10000psi Hydraulic & Manual Choke valves
4 1/16" – 10000psi Hydraulic & Manual Kill valves
Accumulator Unit, NXQ2-L 40/31.5H

- Rig Power Supply
  3x1600 HP Diesel Engine,
  CAT3512B.
  - Power by 3x SR 4B 1900 KVA. [SCR]
- Drill String
  5", NC-50, 2" Weco, Lo-Torq
  3.1/2", NC-38, 2" Weco, 2" Weco
  Safety Equipment

As required by regulations.

• Accommodation

To accommodate 80 persons.