Rig MDC6

JC50D 1500 HP Land Rig

- Related Drilling Depth 15000 ft with 5" drill pipe.
- Substructure
 JJ 315 / 9 X, Height 9m.
- Hook Load
 700,000 lbs (12 lines).
- Setback Load 360,000 lb.
- Mast 148 ft.
- Drawwork
 JC50D, 2000 HP & 1 3/8"
- Auxiliary Brake
 Eaton436WCB2.
- Mud Pump Engine × Qty 2x1600 HP, F1600.
- Travelling Equipment YC315, 315 m tons.
- Rotary ZP375, 37 ½".

Top Drive

Varco TDS 11SA or equiv., 500 Tons.

Well Control Equipment

13.5/8" Bag Preventer 10,000 psi.
13.5/8" Ram single Preventer H2S service.
13.5/8" Ram double Preventer.
4 1/16" – 10000psi Hydraulic & Manual Choke valves
4 1/16" – 10000psi Hydraulic & Manual Kill valves
Accumulator Unit. NXQ2-L 40/31.5H

Rig Power Supply

3x1600 HP Diesel Engine, CAT3512B. Power by 3x SR 4B 1900 KVA. [SCR]

Drill String

5", NC-50, 2" Weco, Lo-Torq 3.1/2", NC-38, 2" Weco, 2" Weco Safety Equipment As required by regulations.

Accommodation

To accommodate 80 persons.