

Rig MDC80

XJ750 (ZEPC)
750HP
Workover Rig

- **Substructure**

DZ195/6.7-S, Height 6.7 M.

Hook Load

1800 KN . (10 Lines).

Setback Load

1100 KN

Mast

JJ19540 , Height 40.2 M

Drawwork,

JC30 , 750 HP &Drilling line 1 ¼"

- **Auxiliary Brake**

PZ40 Hydraulic disc brake.

EATON 324 WCB2, inner circulation.
water cooling.

Rig Power Supply.

2 Engine CAT C-15 - 540 HP

Mud Pump Engine x Qty

1x CAT C27 - 652 KW.

Travelling Equipment

YG180, 200 Ton (10 Lines).

- **Rotary**

ZJ30CZ-04, 20 ½"

Well Control Equipment (SHENKAI)

- 11 " Annular Preventer 5000 PSI.

- 11" Double Ram preventer.

- Drilling Spool: 11" – 5000 Psi.

- 11 " Annular Preventer 3000 PSI.

- 11" Ram double preventer

- Drilling Spool: 11" – 3000 Psi.

- 7 1/16 " Annular Preventer 5000 PSI.

- 7 1/16" Double Ram preventer

- Drilling Spool: 7 1/16" – 3000 Psi.

- 3 1/8" – 5000 psi Hydraulic & Manual

Choke Valves

- 3 1/8" – 5000 psi Manual Kill Valves

- **Drill String**

3 ½ " , NC-38 , G105-13.30 lb/ft. (165
Drill String)

Safety Equipment

As required by regulations.