Rig MDC9

JC70D 2000 HP Land Rig

- Related Drilling Depth 20,000 ft with 5" drill pipe.
- Substructure
 DZ 450 / 9 S1, Height 9 m.
- Hook Load
 1,000,000 lbs (12 lines).
- Setback Load 490,000 lbs.
- Mast 149.24 ft.
- Drawwork
 JC70DB, 2000 HP & 1 ½"
- Mud Pump Engine × Qty
 2x1600 HP, Triplex single acting.
- Travelling Equipment YC450, 1,000,000 lbs.
- Rotary
 ZP375, 37 ½".

Top Drive

Varco TDS 11SA or equiv., 500 Tons.

Well Control Equipment

13 5/8" Bag Preventer 5000 psi. 13 5/8" Ram single Preventer H2S service.

13 5/8" Ram double Preventer sH2S service.

4 1/16" – 10000psi Hydraulic & Manual Choke valves 4 1/16" – 10000psi Hydraulic & Manual Kill valves

Accumulator Unit, NXQ2-L 40/31.5H

Rig Power Supply

3x1600 HP Diesel Engine, CAT3512B. Power by 3x SR 4B 1500 KVA. [VFD]

Drill String

5", NC-50, 2" Weco, Lo-Torq 31/2", NC-38, 2" Weco, Lo-Torq

- Safety Equipment
 As required by regulations.
- Accommodation

To accommodate 80 persons.