

Rig MDCk26

ZJ30/1800CZ8 (BOMCO)
750HP
Workover Rig

- **Substructure**

DZ180/7-X, Height 22.96 ft. (7M)

- **Hook Load**

1800 KN . (10 Lines).

- **Setback Load**

900 KN

- **Mast**

JJ195/39-W1, Height 139 ft.

- **Drawwork,**

JC30BT5, 750 HP & Drilling line 1 ¼"

- **Auxiliary Brake**

Hydraulic disc brake.

- **Rig Power Supply.**

2 Engine CAT C-15 - 540 HP

- **Mud Pump Engine × Qty**

1x CAT C27 - 652 KW.

- **Travelling Equipment**

YG180, 1800 KN (10 Lines).

- **Rotary**

ZP205, 20 ½"

- **Well Control Equipment**

-13 5/8" Annular Preventer 5000 PSI.

-13 5/8" Ram double preventer.

Drilling Spool: 13 5/8" – 5000 Psi.

- 3 1/8" – 5000 psi Hydraulic & Manual

Choke Valves

-3 1/8" – 5000 psi Manual Kill Valves.

- BOP(ROUNGSHONG), BOP control unit
(NOV),choke manifold (NOV)

- **Drill String**

3 ½ " , NC-38 , G105-13.30 lb/ft. (350

Drill String)

- **Safety Equipment**

As required by regulations.